



PAC MACHINE CO., INC.
 1246 GLENDALE AVE.
 SPARKS, NV 89431-5916
 (775) 359-8500 FAX: (775) 359-0818

QUOTE

DATE

2/3/2025

BILL TO:

J-U-B ENGINEERS
 ATTN. DREW MYERS
almyers@jub.com
 775-852-1440

SHIP TO:

PROJECT SITE
 VINTON, CA USA

P.O. NUMBER	TERMS	REP	SHIP	VIA	F.O.B.	PROJECT
	NET 30	CJS	TBD	TBD	ORIGIN	WATER TRANSFER
QUANTITY	DESCRIPTION		PRICE EACH	AMOUNT		

	REQUIREMENT: 1344 GPM @ ~ 100' TDH ~ 7' SUCTION LIFT, CREEK WATER			
	EQUIPMENT:		SYSTEM PRICE:	
1	6" GODWIN CD150S DRI-PRIME DIESEL DRIVEN, TRAILER MOUNT TRASH PUMP, OPEN UNIT SET UP 8" SUCTION X 8" DISCHARGE, 24/7 OPERATION		\$24,787.00	MONTHLY
1	8" X 20' QD SUCTION HOSE*			
1	8" X 20' QD SUCTION / DISCHARGE HOSE			
1	8" QD T W/ 4" DRAIN W/ VALVE			
1	8" F/M QD X 12" FL ADAPTER			
5600'	12" HDPE PIPE, DR17 OR DR21			
1	BOLT/GASKET KITS, MISC FITTINGS TO COMPLETE SYS			
*	CUSTOMER TO PROVIDE SUCTION SCREEN FOR FISH PROTECTION			
TBD	PMC PUMP ENGINE PM (Required Bi-Monthly @ 24/7 Operation) INCLUDES OIL, FILTERS, TRAVEL, LABOR, DISPOSAL		\$2,400.00	PER MONTH
1	ESTIMATED LABOR TO FUSE PIPE & SETUP PUMP INCLUDES (3) PMC RESOURCES @ 8 DAYS (2) FUSION MACHINES, REACH FORKLIFT (Actual Required Labor/Materials to be Billed)		\$46,000.00	
1	ESTIMATED FREIGHT		\$9,800.00	EACH WAY
PLUS TAX & FREIGHT, SUBJECT TO AVAILABILITY				

FREIGHT

T.B.D.

SUBTOTAL

SALES TAX

LABOR

TOTAL

QUOTATIONS ARE VALID FOR 30 DAYS.

PRICES ARE SUBJECT TO CHANGE WITHOUT NOTIFICATION