

Q U O T A T I O N

FROM: Isaacs & Associates  
 3380 Isaacs  
 Walla Walla, WA 99362

Phone: 509-529-2286

Number: Q- 40435  
 Date: 10/23/25  
 Page: 1

QUOTED DS RANCHES LLC  
 TO: PO BOX 18346  
 RENO NV 89511

DELIVER DS RANCHES LLC  
 TO: 6003 COW CAMP ROAD  
 VINTON CA 96135

TERMS: 10%-10 DAYS; NET 30

WELL 11 PROJECT

QTY	PRODUCT CODE	PRODUCT DESCRIPTION	UNIT PRICE	EXTENSION
1.00	XX	10" RIVERSCREEN W/S.S. SCREEN	8978.7600	8978.76
		900 GPM - RIVERSCREEN, ELECTRIC DRIVE 480V 3PH, FOOT VALVE,		
20.00	XC	10" SUCTION HOSE	89.6900	1793.80
4.00	XC	10" HOSE CLAMP	17.4400	69.76
1.00	XF	10" HOSE BARB X 8" FLANGE	487.4400	487.44
1.00	FGR8	FLANGE GASKET, RING 8"	9.0600	9.06
1.00	XN	8" BOLT KIT	14.2800	14.28
1.00	XX	6H-100 CORNELL PUMP 1500 @ 185	23216.6700	23216.67
1.00	XF	6" FLxFL SPOOL WITH 1" FNPT	251.2000	251.20
1.00	XN	6" FLANGE BOLT KIT	13.9300	13.93
1.00	FGR6	FLANGE GASKET, RING 6"	5.9800	5.98
2.00	FI0042	3/4 X 2 NIPPLE GALV	2.9500	5.90
1.00	VBA3/4	BALL VALVE 3/4"	12.2200	12.22
1.00	XV	#9 PRIMER PUMP	395.5600	395.56
1.00	VBFL6	6" BUTTERFLY VALVE-LEVER HANDLE	250.6700	250.67
1.00	VBFXBP6	6" BUTTERFLY VALVE BOLT PACK	23.5100	23.51
1.00	XF	6" FL x 10" FLG CONC REDUCER	372.3600	372.36
2.00	FGR10	FLANGE GASKET, RING 10"	13.4800	26.96
1.00	XV	10" GALV SWING CHECK	722.7300	722.73
2.00	XN	10" FLANGE BOLT KIT 2 1/2	30.7600	61.52
1.00	XF	10" FLG X 10" PIP Z-PIPE 60"	1491.4200	1491.42
1.00	XV	4" PRESSURE RELIEF 51 -120	237.3300	237.33
1.00	XV	4" CONT ACTING AIR/VAC RELIEF	331.5600	331.56
2.00	XFI	4X4 GALV NIPPLE	29.5100	59.02
418.00	XX	10" PIP 100 PSI GSKTD PVC PIPE	9.7200	4062.96
1.00	XF	10" PIP WATERTITE 90 ELBOW	566.6700	566.67
1.00	XF	10" PIP WATER TITE TEE	745.2300	745.23
		FOR CONNECTING TO EXISTING WELL PUMP		
1.00	FFN10	STEEL FLANGE, 1/2" NOMINAL 10"	64.7700	64.77
2.00	FGR10	FLANGE GASKET, RING 10"	13.4800	26.96
1.00	XN	10" FLANGE BOLT KIT	30.7600	30.76
1.00	XV	10" SWING CHECK	722.7300	722.73
400.00	XE	3 CNDCTR 00 ALUM IN 2" DUCT	5.6300	2252.00
2.00	XE	DUCT COUPLER 2"	64.2100	128.42
			SUB:	\$47,432.14
			S/H:	\$ TBD
			QUOTATION TOTAL:	\$47,432.14

ESTIMATED FREIGHT CHARGES \$ 5500.00